




Energy efficiency and economics of the production of microalgae biomass with a flat panel-airlift photobioreactor

Dr. Peter Ripplinger
Subitec GmbH

Content

- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- Integrated production process including Biorefinery
- Comparison of different production systems
- Economics of biomass production in industrial scale
- Summary

Subitec GmbH: the company



Pilot plant, Subitec GmbH, in Stuttgart-Vaihingen (2005)


Subitec GmbH: the company



- Spin-off from the „Fraunhofer-Institut für Grenzflächen- und Bioverfahrenstechnik“ (IGB) in Stuttgart
- Two patent families regarding the Flat Panel Airlift-Photobioreactor granted worldwide
- Pilot plants with E.ON Hanse AG (in Hamburg) and EnBW AG (near Stuttgart)
- Projects funded by DBU (Deutsche Bundesstiftung Umwelt) the state Baden-Württemberg

Position in the value chain

Product development with academic and industrial partners







Products and Services



- Systems for the cultivation of microalgae based on 5 L, 9 L, 33 L und 180 L-FPA-Reactors
- R&D partner for biorefinery concepts based on algae biomass
- Production of algae biomass for the cosmetic and pharma industry and for product development

Microalgae cultivated in the FPA-Reactor


	Lab scale	
	max. DW (g/l)	∅ Prod. (g DW/l*d)
Marine algae		
Isochrysis spec. (clone T.iso)	10	0,5
Nannochloropsis oculata	13	1
Tetraselmis suecica	16	0,6
Platymonas subcordiformis	12	0,5
Other algae (sweet water)		
Chlorella vulgaris	12	0,8
Chlorella sorokiniana	12	1,3
Eigenisolat DSN 5.1	16	0,7
Haematococcus pluvialis	2,5 ^a	0,5
	5 ^b	0,3
Phaeodactylum tricornutum	25 ^d	1,5
	12 ^e	0,9



Flat Panel Airlift (FPA) – Photobioreactor



- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- Integrated production process including biorefinery
- Comparison of different production systems
- Economics of biomass production in industrial scale
- Summary



Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)




Light supply in dense algae cultures

Problems:

- Inhibition of photosynthesis
- Optimal light intensity is 5 to 10-fold lower than the natural light intensity
- Limitation due to dense cultures

Solution:

- Continuous transportation of the algal cells through the different zones
- Use of the „flashing light effect“




FPA technology

Process engineering

- efficient light supply to all cells
- complete homogenous intermixing
- low mechanical stress to the cells
- simple temperature and pH control
- efficient gas exchange

Cost-effectiveness

- high volumetric productivity
- high cell densities
- high reactor volumes
- low capital and operating costs
- high reliability




Halfshells of the FPA made from deep-drawn plastic sheets



static mixers
flow

FPA-Reactor, 3. Generation (2008)



<u>Technical data:</u>	Hights	270 cm	Volume	180 l
	Lengths	175 cm	Material	PVC or PETg
	Thickness	5 cm		



Advantages of the new FPA - Reactor




- Reduction of production costs of the bioreactor (ca. 1.000 €/m³)
- Could be used over a 5 year period (new materials)
- No problems with leakages (Twin-Sheet technology)
- Reduction of the energy consumption (from 477 W/m³ to 100 - 200 W/m³)

Pilot plants



- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- **Pilot plants**
- Integrated production process including Biorefinery
- Comparison of different production systems
- Economics of biomass production in industrial scale
- Summary



Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)




Pilot plants



- since 2005: Pilot plant in Stuttgart-Vaihingen, based on 33 L-Reactors for the cultivation of Haematococcus and Phaeodactylum
- May 2008: Start of the pilot plant in Eutingen-Weitingen
Multipurpose plant, based on 180 L-Reactor,
Total volume: ca. 4 cbm
- June 2008: Start of the pilot plant in Hamburg-Reitbrook,
two modules with 4 x 180 L-Reactors
- 2009: Pilot plant in a greenhouse (4 modules of 6 x 180 L-Reactors),
Production plant with 180 cbm total volume,
ca. 0,5 – 0,7 ha, in Spain

Flow chart – production modul



Subitec GmbH



Pilot plant in Eutingen-Weitingen (2008)




Subitec GmbH



Pilot plant in Hamburg-Reitbrook in cooperation with E.ON Hanse (2008)



Modul with 8 x 180 L FPA reactors





Length of the module: ca. 20 m



Sceme of a 5 x 20 module



Pilot plant in Spain (180 m³)







Basic process of the pilot plants

CHPs

- in Hamburg: natural gas
- In Eutingen-Weitingen: biogas


Cultivation of microalgae



Integrated production process including biorefinery




- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- **Integrated production process including biorefinery**
- Comparison of different production systems
- Economics of biomass production in industrial scale
- Summary




Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)



Integrated production process for microalgae biomass




Biorefinery concepts for algae biomass



increasing energetical usage




Total energy content of products derived from 1 kg algae biomass



- 35 % of lipids to produce 0,35 kg FME
- 50 % of carbohydrates to produce 0,225 kg of ethanol
- 0,8 m³ of biogas derived from 1 kg dry algae biomass



Total energy content of product derived from 1 kg algae biomass




- 35 % of lipids to produce 0,35 kg FME
- 50 % of carbonhydrates to produce 0,225 kg of ethanol
- 0,8 m³ of biogas derived from 1 kg dry algae biomass



Comparison of different production systems



- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- Integrated production process including Biorefinery
- **Comparison of different production systems**
- Economics of biomass production in industrial scale
- Summary



Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)



Is net energy production achievable?



Energy content of algae biomass

- energy input for cultivation

Net energy production ???


Comparison of different culture systems



	Open ponds	Tubular	Flat-Panel-Airlift-Reaktor (FPA)
Risk of contamination	high	low	low
Volumetric productivity	low	medium/high	high
Cell density	very low	medium/high	high
Energy input	low	high	low
Capital costs	low	high	medium



Comparison of the energy input of different production systems




* Daten aus Sierra et al. 2007

** abgeschätzt nach Angaben Pumpenleistung, IGV

§ Angaben für 165 L-FPA



Comparison of the energy input per kg DW of different production systems



Net energy production is achievable!




It can be proven
that a net energy production is only achievable with
a Flat Panel Airlift-Bioreactor system.



Pressure losses for the FPA-System

Total working pressure = Sum of partial pressure losses




Energy Input: 100 – 200 W / m³

Possible optimisations:

1. Membrane
2. robust algae cultures / mixed cultures
3. Use of industrial processes, which deliver CO₂ under pressure
4. Airflow adapted to light intensity/actual productivity




Total energy content of product derived from 1 kg algae biomass




- 35 % of lipids to produce 0,35 kg FME
- 50 % of carbonhydrates to produce 0,225 kg of ethanol
- 0,8 m³ of biogas derived from 1 kg dry algae biomass



Net energy gain with FPA at 0,8 bar working pressure




Net energy gain with FPA at 0,5 bar working pressure



Economics of biomass production in industrial scale




- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- Integrated production process including Biorefinery
- Comparisation of different production systems
- **Economics of biomass production in industrial scale**
- Summary



Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)



Value and market size for algae biomass in different market segments



Annual productivity in different climates

climatic zone	productive days per year	Productivity per ha and year (t DW / ha*a)	
		with ø 1g DW/l*d	with ø 0,8 g DW/l*d
tropical	365	137	110
Mediterranean	300	113	90
central europe	240	90	72
Stuttgart	200	75	60

Calculated for the 180 L-FPA and 2,50 m distance between the modules

productivity > 100 t TS / ha * year



Production and capital costs

For a 1 ha plant:

- capital costs 1'500'000 € (25% for FPA-photobioreactors)
- productivity 120 t / year
- production costs:

Depreciation	2.000	€ / t ODW
Electricity	200	€ / t ODW
Nutrients	1.500	€ / t ODW
Personnel costs	500	€ / t ODW
Total (incl. dep.)	4200	€ / t ODW


For a 100 ha plant: ????



Summary



- Subitec GmbH: the company
- Flat Panel Airlift (FPA) – Photobioreactor
- Pilot plants
- Integrated production process including Biorefinery
- Comparison of different production systems
- Economics of biomass production in industrial scale
- **Summary**



Pilotanlage der Subitec GmbH in Stuttgart-Vaihingen (2005)



Summary

- Third generation FPA-Reactors is available since 2008
- 2 pilot plants started operation in 2008
- At least 4 pilot plants are planned for 2009
- Capital costs and running costs for production plants could be diminished radically
- Net energy gain is possible
- Production of fine chemicals in large scale is possible today
- Production of algae biomass for feed, lipid production and for energetical use is achievable in 3 – 5 years



Thanks for your kind attention!